



NAYA RAIPUR DEVELOPMENT AUTHORITY

**Tender Document for the
RCC Structure and allied Civil work for Installation of
proposed Statue of Pt. Dindayal Upadhyay at rotary near
Capital Complex of Naya Raipur**

(Following Three-Envelope Tender Procedure)

**Schedule – A
Price Tender
To be submitted in ENVELOPE-3**

NIT No.: 93/STATUE/EEC-III/CE(E)/NRDA/2016-17, Naya Raipur

Dated: 12.08.2016

Issued by: Chief Executive Officer,
Naya Raipur Development Authority (NRDA)
Paryavas Bhawan, North Block Sector- 19,
Naya Raipur- 492 002, Chhattisgarh
Tel No: + 91 771 2512500; Fax No.: +91 771 2512400.
Website: www.nayarapur.gov.in

Tender Document Contains

- (a) Only schedule "A" and Section-I of schedule "D" are to be filled & signed by the tenderer
 (b) All the certificates as per pre qualification criteria shall be appended with relevant forms of schedule "D"

1. PART ONE (NRDA F-1)-(Attached herewith, to be submit along the tender)

Part (A)

- a) Press Notice
 b) Detailed NIT

Part (B)

a) Schedule-A

- (i) Cost Abstract
 (ii) Bill of Quantities

- b) Schedule-B –NIL
 c) Schedule-C –NIL
 d) Schedule-D

Section-I..... Technical tender forms

- (i) Letter of Technical Tender
 (ii) Tenderer's Information Sheet
 (iii) Annual Turnover
 (iv) Specific Construction Experience
 (v) Declaration
 (vi) Check list for Technical tender evaluation
 (vii) Return Of EMD
 (viii) Integrity Pact

Section –IIScope of work

Section –III..... Technical specifications of work

Section –IV..... Special Conditions of Contract

Section –V..... List of approved makes

Section –VI..... Drawings

- e) Schedule-E
 f) Schedule-F

2. PART TWO (NRDA F-2/3)-Standard form (Not Attached herewith, and not to be submitted along the tender) Important note: - Link site <http://nayaraipur.com/documents/gcc.pdf>

1. General Guidelines
2. Tender
3. General rules and directions
4. Conditions of contract
5. Clauses of contract
6. Model rules relating to labour, water supply and sanitation in labour camps safety code
7. Contract forms
 - (a) Draft Format for Performance Security
 - (b) Earnest Money Deposit Form (Bank Guarantee)
 - (c) Format of Contract Agreement
 - (d) Draft Format for Performance Guarantee for Water Proofing and Anti-termite Works
 - (e) Indemnity Bond
 - (f) Indenture Bond
 - (g) Notice for Appointment of Arbitrator

Signature of Contractor.....

Signature of NRDA.....

8. Proforma of schedules (Schedule 'A' to Schedule 'F')

**Naya Raipur Development Authority (NRDA)
Raipur, Chhattisgarh**

Document details

Name of work : "RCC Structure and allied Civil work for Installation of proposed Statue of Pt. Dindayal Upadhyay at rotary near Capital Complex of Naya Raipur".

Name of Tenderer:

Details

- a) Cost of Tender Document : Rs
- b) EMD : Rs

Signature of Tenderer

Date: _____

Signature of Contractor.....

Signature of NRDA.....

BILL OF QUANTITY

RCC Structure and allied Civil work for Installation of proposed Statue of Pt. Dindayal Upadhyay at rotary near Capital Complex of Naya Raipur

Sr. No.	Description of Item	Unit	Quantity	Rate in INR	Rate in words (in INR)	Amount in Rs.
1	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete					
a	Thermo-Mechanically treated bars (FE 500)	Kg	2100.00			Rs. -
2	Excavation in all types and sizes of foundations, trenches and drains or for any other purpose with all lead and lift including seperation of usefull soil for refilling and stacking & levelling of same, and disposal of surplus excavated stuff and spoils beyond NRDA boundries or as directed by Engineer In-charge including souring, dewatering, surface dressing, etc., complete as per direction of Engineer In-charge.					
a	In all types of soil	Cum	25.00			Rs. -
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.					
a	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	Cum	2.50			Rs. -

Sr. No.	Description of Item	Unit	Quantity	Rate in INR	Rate in words (in INR)	Amount in Rs.
4	Providing and laying design mix reinforcement cement concrete with crushed graded stone aggregate 20mm nominal size using batching plant, transit mixer and concrete pump, in all works upto floor five level excluding cost of reinforcement and form work.					
a	M-25	Cum	32.00			Rs. -
5	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering from deposited stack spoils.	Cum	15.00			Rs. -
6	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal up to floor five level, for:					
a	Foundations, footings, base of columns and plinth beam in any shape and size.	Sqm	6.00			Rs. -
b	Wall of any thickness including attached pilasters, buttresses etc.	Sqm	65.00			Rs. -
c	Columns, Pillars, Piers and likes- rectangular or square in shape	Sqm	35.00			Rs. -
d	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	Sqm	100.00			Rs. -

Sr. No.	Description of Item	Unit	Quantity	Rate in INR	Rate in words (in INR)	Amount in Rs.
e	Edge of slab, breaks in floor and walls upto 200mm.	Metre	30.00			Rs. -
7	Extra for additional height every 1m or part thereof where height of staging for formwork exceeds 4.0 m, with adequate bracing, propping etc at all levels, for suspended floor, roof, landing, beam and balcony. (only plan area is to be measured)	Sqm	75.00			Rs. -
8	15mm thick Granite work (machine cut, table rubbed & mirror polished) for wall lining (veneer work) in cement mortar 1:3 (1 cement : 3 coarse sand) including pointing with cement mortar 1:2 (1 white cement: 2 marble dust) mixed with matching pigment. (Area of slab should be over 0.5 sqm).					
a	Granite stone black	Sqm	50.00			Rs. -
b	Granite stone lakha red/ shahi red	Sqm	50.00			Rs. -
9	Extra for laying of any type of stone in flooring in strips:					
a	Upto 100 mm width	Sqm	10.00			Rs. -
b	Above 100 mm and upto 150 mm	Sqm	5.00			Rs. -

Sr. No.	Description of Item	Unit	Quantity	Rate in INR	Rate in words (in INR)	Amount in Rs.
10	Extra for fixing marble /granite stone in facia and drops of width upto 150 mm with epoxy resin based adhesive instead of cement mortar including cleaning etc. complete.	Metre	100.00			Rs. -
11	Extra for providing edge moulding to 15mm thick stone counters, vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge					
a	Granite work	Metre	100.00			Rs. -
12	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.	Sqm	42.00			Rs. -
(a)	Size upto 200x300mm					
13	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete. (a) SS Grade 304	Sqm	300.00			Rs. -

Sr. No.	Description of Item	Unit	Quantity	Rate in INR	Rate in words (in INR)	Amount in Rs.
14	Dismantling of existing fountain and adjoining structure / tiles / RCC / CC foundation including safe removal of pipes, cables, light fittings, nozzles etc. so as to prepare the area for boring & casting of under reamed RCC piles and related RCC structures. (Qty. of work as per requirement of site)	Job	1.00			Rs. -
15	Providing and fixing Glass mosaic tiles at finished plain wall surface of size 20 mm x 20 mm x 4 mm in all colour, design, fixing in customize design as per direction of Engineer-in-Charge. The glass mosaic tiles to be fixed on the wall surface with the help of approved adhesive applied at the rate of 2.5 kg per sqm and grouting of the same. The rate is inclusive of all operation, material and required pattern approved by Engineer-in-Charge:	Sqm	360.00			Rs. -
	Total					Rs. -