

CORRIGENDUM-2

No.: 111/ES/VB/EEC1/NRDA/2013, Raipur, dated: 18.2.2013

Following criteria & dates in NIT No: 04/ES/VB/ EEC1/NRDA/2013, Raipur, dated: 04/2/2013 "Supplying and fixing of Blind & other miscellaneous works in Mantralaya Building at Capitol Complex, Naya Raipur" have been modified –

Item. No.	ITEM DESCRIPTION IN PRICE-BID	MODIFIED AS
1	Providing & Fixing Verticle blind complete as per specification and as directed by engineer-in-charge.	Providing & Fixing Verticle blind including support, control and movement mechanism complete as per Specification no. 5.2.28.1 & 5.2.28.3.1 and as directed by engineer-in-charge.
2	Providing & Fixing Opaqe Roller blind complete as per specification and as directed by engineer-in-charge.	Providing & Fixing Opaqe Roller blind including support, control and movement mechanism complete as per Specification no. 5.2.28.1 & 5.2.28.3.2 and as directed by engineer-in-charge.
3	Providing & Fixing Translucent Roller blind complete as per specification and as directed by engineer-in-charge.	Providing & Fixing Translucent Roller blind including support, control and movement mechanism complete as per Specification no. 5.2.28.1 & 5.2.28.3.2 and as directed by engineer-in-charge.
4	Providing & Fixing Fabric Curtain complete as per specification and as directed by engineer-in-charge.	Providing & Fixing Fabric Curtain P-line/Smooth-line including support, control and movement mechanism complete as per Specification no. 5.2.28.1 & 5.2.28.3.2 and as directed by engineer-in-charge. (Basic rate of Fabric is Rs. 350.00 per Sqm.) .
5	Providing & Fixing Plastic chairs complete as per specification and as directed by engineer-in-charge.	Providing & Fixing monolithic moulded Plastic seat and back (minimum seat dimension of 45cm x 45cm and minimum back height of 35cm) as per approved make GODREJ Model no. MPC-101 or similar approved equivalent of approved color. The seat shall be fixed on the top of Granite ledge by machine drilling and fixing with steel blots/ screws including MS flat 150mm x 40 mm x 4 mm (thick) and washer complete as per specification and as directed by engineer-in-charge.
6	Providing & Fixing twin wall semi transparent polycarbonate compact sheet roofing complete as per specification and as directed by engineer-in-charge.	Providing and fixing 6mm thick twin wall semi transparent polycarbonate compact sheet roofing of approved colour at all heights to make any normal shape of roofing / covering of any pitch and fixing with specially designed powder coated aluminium section with 60mm wide flange of standard design weighing not less than 1.1 kg/ m at spacing not more than 1.2 m centre to centre with EPDM gasket and silicon sealant on all four edges of aluminium section fixed with self drilling stainless steel screws all complete including aluminium edge angle 40 mm x 40 mm x3mm as per specification and as per direction of Engineer-in-Charge. (If required MS frame shall be provided by the contractor. Payment for MS frame shall be paid extra).

7	New item	Providing and fixing Hot finished Seamless Welded Tubes Steel work in tubular structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.
8	New item	Extra for hoisting trusses and placing in position over height above 5m for every 2.5 m height or part thereof.
9	Last date of submission of sealed tender: 22.2.2013 upto 15:00 hours	Last date of submission of sealed tender: 25.2.2013 upto 15:00 hours
10	Opening of technical bid: 20.3.2012 after 16:00 hours.	Opening of technical bid: 25.2.2013 after 16:00 hours.
11	Opening of price bid: 22.3.2012 (tentative).	To be intimated later.

**NOTE: 1. REVISED VOLUME-II: PRICE-BID/BILL OF QUANTITY IS APPENDED HEREWITH.
2. DULY FILLED VOLUME-II: PRICE-BID/BILL OF QUANTITY SHALL BE SUBMITTED IN ENVELOPE-3.
3. Other conditions remain same.**

Chief Executive Officer



NAYA RAIPUR DEVELOPMENT AUTHORITY



NIT NO.: 04 /ES/VB/ EEC1/NRDA/2013, RAIPUR, DATED: 04/2/2013

TENDER

FOR

**SUPPLYING AND FIXING OF BLIND & OTHER MISCELLANEOUS
WORKS IN MANTRALAYA BUILDING AT CAPITOL COMPLEX,
NAYA RAIPUR**

VOLUME II

Revised Price Bid / BOQ.

(To be submitted with Envelope-3)

Name of work: Supplying and fixing of Blind & other miscellaneous works in Mantralaya Building at Capitol Complex, Naya Raipur

NIT No.: 04 /ES/VB/ EEC1/NRDA/2013, Raipur, dated: 04/2/2013

Volume-2: Revised Price Bid (BILL OF QUANTITIES)

Item No.	ITEM DESCRIPTION	UNIT	Qty.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6
1	Providing & Fixing Verticle blind including support, control and movement mechanism complete as per Specification no. 5.2.28.1 & 5.2.28.3.1 and as directed by engineer-in-charge.	Sqm	2500		
Rupees in word.....					
2	Providing & Fixing Opaqe Roller blind including support, control and movement mechanism complete as per Specification no. 5.2.28.1 & 5.2.28.3.2 and as directed by engineer-in-charge.	Sqm	100		
Rupees in word.....					
3	Providing & Fixing Translucent Roller blind including support, control and movement mechanism complete as per Specification no. 5.2.28.1 & 5.2.28.3.2 and as directed by engineer-in-charge.	Sqm	100		
Rupees in word.....					

Signature of Contractor.....

Signature of NRDA.....

Item No.	ITEM DESCRIPTION	UNIT	Qty.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6
4	Providing & Fixing Fabric Curtain P-line/Smooth-line including support, control and movement mechanism complete as per Specification no. 5.2.28.1 & 5.2.28.3.2 and as directed by engineer-in-charge. (Basic rate of Fabric is Rs. 350.00 per Sqm.).	Sqm	200		
Rupees in word.....					
5	Providing & Fixing monolithic moulded Plastic seat and back (minimum seat dimension of 45cm x 45cm and minimum back height of 35cm) as per approved make GODREJ Model no. MPC-101 or similar approved equivalent of approved color. The seat shall be fixed on the top of Granite ledge by machine drilling and fixing with steel bolts/ screws including MS flat 150mm x 40 mm x 4 mm (thick) and washer complete as per specification and as directed by engineer-in-charge.	Nos.	300		
Rupees in word.....					

Signature of Contractor.....

Signature of NRDA.....

Item No.	ITEM DESCRIPTION	UNIT	Qty.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6
6	Providing and fixing 6mm thick twin wall semi transparent polycarbonate compact sheet roofing of approved colour at all heights to make any normal shape of roofing / covering of any pitch and fixing with specially designed powder coated aluminium section with 60mm wide flange of standard design weighing not less than 1.1 kg/ m at spacing not more than 1.2 m centre to centre with EPDM gasket and silicon sealant on all four edges of aluminium section fixed with self drilling stainless steel screws all complete including aluminium edge angle 40 mm x 40 mm x3mm as per specification and as per direction of Engineer-in-Charge. <i>(If required MS frame shall be provided by the contractor. Payment for MS frame shall be paid extra).</i>	Sqm	400		
Rupees in word.....					
7	Providing and fixing Hot finished Seamless Welded Tubes Steel work in tubular structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.	Kg	300		
Rupees in word.....					

Signature of Contractor.....

Signature of NRDA.....

Item No.	ITEM DESCRIPTION	UNIT	Qty.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6
8	Extra for hoisting trusses and placing in position over height above 5m for every 2.5 m height or part thereof.	Kg	300		
Rupees in word.....					
TOTAL				Rs.	
Amount in words: Rupees.....					

Signature of Contractor.....

Signature of NRDA.....