

Reply to Pre Bid Queries for the
“Landscape Development of Serikhedi Interchange at Naya Raipur”

Sr.No	Bidder Query	Clarification
1	The detail list of plants shown in the drawing no.MDV-IN-LN-GE-TD-0006 is not matching with the BOQ (item no. 26) given in the Tender, please clarify?	It is clarified that, Item 26 is correct with reference to drawings and BoQs.
2	In the Drawing, one plant name not mentioned and shown local palm, so please give the height and scientific name of the plant?	It is clarified that, Botanical name of the plant is “Aiphanes caryotaefolia” and shall have a minimum height of about 5 feet.
3	In the BOQ and drawing solenoid valves and controller not shown but details given in the specification for the same, so please clarify?	It is clarified that, automation not considered in the item.
4	In the drawing the paver block shows Glossy interlock but in the BOQ it is mentioned colour pigmented interlock block, please clarify?	It is clarified that, the item no. 16 should be read as <i>“Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm. Glossy Coloured pigment precast interlock concrete blocks made out of rubber moulds”</i> instead of <i>“Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm. Coloured pigment precast interlock concrete blocks.”</i>
5	Kindly clarify the process of electricity connection for pump and main panel board.	It has been clarified, that a) During construction phase, Clause 4 of Special conditions of contract shall be applicable b) Power connection charges and monthly bill during O& M period shall be paid by contractor and shall be reimbursed by the NRDA on submission of proof of actual payment.
6	Kindly provide the list of nominated subcontractor (if any) in NRDA for different works.	It has been clarified in the detailed NIT in Clause 3.2 in Note (a)
7	Kindly provide the 5% security deposit rules for this tender.	No change from the condition mentioned in the tender.
8	Kindly provide the detail information about various deductions in the	It is clarified in the relevant clause of GCC.

Sr.No	Bidder Query	Clarification
	running bill for this tender.	
9	After viewing the BOQ and NIT we understand that the work of soil cutting & filling and other works are for limited period but in the detail NIT it is mentioned to keep minimum nos. of machinery like JCB, Poclairn etc(clause 47) which will surely increase the cost of work, please clarify?	It is clarified that, the necessary equipments and machineries, If required have to be deployed in the interest of work.
10	In the detail NIT it is clearly mentioned that only EMD & cost of Tender form should be there, but as per the clause 49 it is mentioned to submit the list of machinery with manufacturer, registration no. etc. please clarify?	Clause 49 is not a part of mandatory eligibility criteria. However, see clarification in Sr. No. 9 above.
11	The item 98 in BoQ is not clearly defined	It is clarified that , Item no. 98 may be read as "Supply, erection, testing and commissioning of Bush light comprises of Polyester black powder coated die cast aluminium with spike to install. Luminaire (120mm dia) E27 lamp holder with aluminium reflector (Ingress Protection: IP 67 for lamp housing) suitable for 50watt DH lamp, accessories are wired upto the terminal block. complete with Grouting bolts, PCC foundation and earthing as required and as per direction of Engineer-in-charge all complete" Instead of "Supplying, installation, testing and commissioning of Lawn lights (Landscape luminaries) complete with Grouting bolts, PCC foundation and earthing. As required. (i) Lawn light as specified. 150 PAR 16 (1 X 50W. lamp)"
12	The 150mm dia in item 35 of BoQ is not clearly	It is clarified that , Item no. 35 may be read as "Casing assembly composed of 150 mm dia ISI marked UPVC blank and screened pipes. (i) 150 mm diameter of 150mm length" instead of "Casing assembly composed of 150 mm dia ISI marked UPVC blank and screened pipes. (i) 150 mm dia."
13	Error in Item no 117 (i) and (ii)	It is clarified that , Item no. 117(i) may be read as "4x10sq.mm." instead of "2x4sq.mm."
14	Error in Item no 117 (ii)	It is clarified that , Item no. 117(ii) may be read as "4x16sq.mm." instead of "2x16sq.mm."
15	Spreading of good earth item is not available.	It is clarified that , Item no. 17 may be read as "Supplying ,stacking and spreading of good earth at site including royalty, loading, unloading and carriage upto 10 km (earth measured in stacks will be reduced by 20% for payment)" instead of "Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 10 km (earth measured in stacks will be reduced by 20% for payment)"